HASSAN DIVISION.

Dated Camp Sri Ramadevar Dam, 13th April 1912.

Notice is hereby given that sealed tenders will be received at the office of the Executive Engineer, Hassan Division, up to 30th April 1912, for restoring Herekadlur Gosadinkere tank, Registered No. 551, Hassan Taluk. An approximate estimate of quantities is given below. These quantities are not guaranteed. The work should be completed by the end of June 1913.

2. The plans, detailed estimate and conditions may be seen at the Executive Engineer's office at Hassan between the hours of 11 A.M. and 5 P.M.

3. Tenders should be submitted on printed forms which may be obtained from the Executive Engineer. The tenders should be accompanied by a statement in the form given below, showing the rates at which the different items specified will be executed.

4. Each tender must be accompanied by a deposit of rupees two hundred in cash or Government Promissory Notes, as earnest money, and be superscribed "Tender for restoring Herekadlur Gosadinkere tank, Registered No. 551, Hassan Taluk," in default of which, tenders will be rejected.

5. The final acceptance of any tender will rest with the Superintending Engineer, Northern Circle, who does not bind himself to accept the lowest or any tender or to assign any reason whatever for the rejection of any tender.

6. Within eight days of the acceptance of the tender, the successful competitor will be required to execute the usual contract bond; in default of which, his tender will be considered cancelled, and his earnest money will be forfeited.

7. The name of the successful competitor, whose tender has been accepted, will be posted on the notice board in the Executive Engineer's office in due course. No enquiries regarding the acceptance or rejection of a tender will receive any reply.

8. On acceptance of one of the tenders, the earnest money on rejected tenders will be returned.

Detailed abstract estimate of restoring Herekadlur Gosadinkere tank, Registered No. 551, Hassan Taluk.

No.	*Items of work*	*Unit*	*Quantity*
	Bund.		
	Earthwork	C. yd.	10,444
	Turfing	S. yd.	14,808
	New stone work	C. yd.	2,069
	Old stone with new jelly	,,	253
	Gravel backing	,,	924
	Removing and refixing old grade stones with bed slabs, including cutting figures, etc.	Each	36
	Vis-a-vis stones	,,	36
	B. M. stones	,,	2
	Registered number and date stone	,,	1
	Gauge stones	,,	2
	Jungle clearing	Lump sum.	
	Breaching the bund and refilling	Do	
	Left waste weir 210 feet long.		
	Earthwork	C. yd.	1,033
	Burnt brick in surki	C. ft.	2,587
	Surki plastering	Sq.	11·00
	Burnt stone slabs	S. ft.	355
	New stone work	C. yd.	256
	Old stone work with new jelly	,,	82
	Earthwork, draft clearing	,,	660
	Right waste weir 60 feet long.		
	Earthwork, excavation	C. yd.	180
	Burnt brick in surki	C. ft.	597
	Burnt stone slabs	S. ft.	130
	Surki plastering	Sq.	4·00
	Rough stone work, new	C. yd.	49
	Old stone work	,,	58
	Earthwork, draft clearing	,,	1,900

A. PUTTASWAMIAH,
Assistant Engineer in charge.